



REGARDING : :

Ref 020.00.115: Insulated telescopic pike-pole

TEST CERTIFICATION

We undersigned, GROUPE LEADER SAS– France, certify that these equipments have fulfilled required tests in compliance: **ICE 60855 (Insulating foam-filled tubes)**, **IEC 61235 (Insulating hollow tubes)**

➤ **Type test**

Tests are performed according to the table II paragraph 5 (IEC 60855)

Tests are performed according to the table 2 paragraph 7 (IEC 61235)

➤ **Routine test**

All tubes shall be subjected to routine tests as follow:

-External visual inspection

-Dielectric test:

- 100 kV/30cm for foam filled tubes
- 50 kV/30cm for hollow tubes

➤ **Sampling test**

Sampling test shall be carried out on the batch of tubes as follows

-Dimensional check

-Mechanical test

-Dielectric test after exposure to water

Michael STEEN
R&D manager

2013 march 11th